

## PV system

### HIGH OUTPUT ENERGY SYSTEMS



## PV Hybrid System Jabi Lake Mall 609.84 kWp

| Technical information         |   |
|-------------------------------|---|
| <b>PROJECT</b>                | Jabi Lake Mall on behalf of CrossBoundary Energy            |
| <b>LOCATION</b>               | Abuja, Nigeria Nigeria – Jabi Lake Mall                     |
| <b>MODEL</b>                  | Rooftop project with Soventix Hybrid Controller Integration |
| <b>SIZE</b>                   | 609.84 kWp  |
| <b>MODULES</b>                | Akcome 330Wp SK6612P  |
| <b>INVERTER</b>               | Huawei SUN2000-60KTL  |
| <b>COMPLETED</b>              | April 2020  |
| <b>ELECTRICITY GENERATION</b> | ~896.000 kWh p.a.*  |

\*Yearly generation may differ, as solar output is depending on actual load profile.